

Connecticut Precast Corp.

Manufacturers of Concrete Products

555 Fan Hill Road, Monroe, CT 06468 Telephone (203) 268-8688 Fax (203) 452-1007


www.ctprecast.com

Pump Chamber

MODEL	LIQUID	LENGTH	WIDTH	INVERT	HEIGHT	WEIGHT
NO	CAPACITY	L	W	I	H	(LBS.)
P5500(7X16)	5500	17'-0"	8'-0"	7'-4"	8'-9"	


PRECAST CONCRETE 5500 Gallon Capacity 7'-0" X 16'-0" (H20 Loading)






NOTES:

- Concrete 4,000 PSI @ 28 DAYS.
- 2. Meets or exceeds state and local requirements.
- 3. All shiplap joints sealed with Butyl Rubber.
- 4. Load Capacity: AASHTO HS-20.5. Single compartment chamber.
- 6. Side inlet pipes shall extend to clean-out cover.
- Maximum fill over top of tank 3 feet.
- 8. Chamber shall be marked with manufacturer name, and phone no., tank capacity, date of manufacture, and ASTM C1227 conformance.
- 9. Invert shown in table for $\phi4"$ PVC. Pipe locations and sizes may change due to project conditions.





**=Nominal Dimension. Slight variation in dimensions may occur due to tapering for manufacturing purposes